

The City of Rock Falls is seeking bids for the remodel of the restrooms in City Hall, Rock Falls Chamber and Fire Department.

Bid packets can be picked up at the Rock Falls Building Department or downloaded at WWW.RockFalls61071.net. A pre bid meeting is scheduled for June 11th 2019 at 9am at Rock Falls City Hall 603 W 10th Street. Bid opening is scheduled for 10 am on June 25th 2019 at 603 W 10th Street Rock Falls, IL 61071.

Bids must be submitted in a sealed envelope, labeled with City of Rock Falls Restroom Remodel. Bids must be submitted by 10 am June 25th 2019.

Construction must start within 45 days of the awarded bid and be completed by November 15th 2019.

A performance bond for the bid amount will be required upon award of the bid.

The public body or other entity awarding the contract shall cause to be inserted in the project specifications and the contract a stipulation to the effect that not less than the prevailing rate of wages as found by the public body or Department of Labor or determined by the court on review shall be paid to all laborers, workers and mechanics performing work under the contract.

When a public body or other entity covered by this Act has awarded work to a contractor without a public bid, contract or project specification, such public body or other entity shall comply with subsection (a-1) by providing the contractor with written notice on the purchase order related to the work to be done or on a separate document indicating that not less than the prevailing rate of wages as found by the public body or Department of Labor or determined by the court on review shall be paid to all laborers, workers, and mechanics performing work on the project.

Amendments to the bid can be found at WWW.RockFalls61071.net

Bid No. 1

Rock Falls Chamber Restroom Remodel

601 W 10th St, Rock Falls, IL 61071

All finished remodel bathroom to comply with ADA

Demolition:

Remove all fixtures, sinks toilets, grab bars, stall dividers, mirrors, lighting ect.

Remove all wall and floor ceramic tile.

Demo door opening.

Wall finish:

Install ½ inch moisture resistant green board dry wall on all walls, tape and apply smooth finish.

Prime and Paint all walls, city of Rock Falls to supply color choice.

Ceiling finish:

Install ½ inch dry wall on all ceilings, tape and apply smooth finish.

Prime and Paint all walls, city of Rock Falls to supply color choice.

Flooring:

Level all floors and prep for ceramic tile install.

Install Bell Vista 13X13 Smoke ceramic tile in a brick set pattern with a Bell Vista Octagon Mosaic 2 inch Smoke border around all floors 12 inches from wall. Tec #25 sanded grout.

Install Bell Vista Bullnose 3x13 smoke (p43e0) Tec #25 sanded grout.

Plumbing:

Adjust all plumbing per attached ADA layout for bathroom fixtures.

Install floor drains per state of Illinois plumbing Code.

Adjust all floor drains level with new floor tile. Repair all demolition from drain install.

Install new shut offs on all sinks and toilets.

Install Mansfield 410 urinals with a Sloan186-xl and Zurn Zerk-cpm auto flush eye. White color

Install Madera 1.6 gpf ADA EverClean Toilet with a Exposed Manual valve system Mod;2854.016.020 Finish White (020)

Install a 47 Inch Wall-Mount Double Sink Stone Resin Matte White Trough Bathroom Sink with Two Faucet HoleJ020828-GLOSSY_WHITE in the women restroom (<https://www.homary.com/47-inch-wall-mount-double-sink-stone-resin-matte-glossy-white-trough-bathroom-sink-with-two-faucet-hole.html>)

Install a Moen Model # WS84414MSRN Spot resist Brushed nickel faucet

Install a Mona Wall Mounted White single hole sink Model # CeraStyle 064200-U-One Hole in the men's restroom with a Moen Model # WS84414MSRN Spot resist Brushed nickel faucet.

Under sink plumbing shall have ADA protection installed.

All plumbing to be inspected and approved by the Illinois Sate Health department.

Fixtures:

Install a Rubbermaid Horizontal Baby Changing Station FG781888PLAT in the Women restroom

Install a Bradley Angle Frame Mirror 18x36 over each sink.

Install a Lavex Stainless steel 400 C-Fold Surface mounted Paper Towel Dispenser.

Install solid plastic Stall dividers HDPE City to have choice of color.

Install brushed nickel grab bars per ADA requirements.

Existing hand driers shall be reinstalled.

Existing ceiling vent fans shall be reinstalled.

All fire alarm system to be reinstalled

All Ptech heating and cooling units to be reinstalled.

Install Toilet paper dispensers Kimberly Clark Coreless Double Roll Tissue Dispenser, 11w x 6d x 7 5/8h, Smoke/Gray - KCC09604

Install black Betco Clario hand soap dispensers.

Door:

Install a 36 inch by 80 flush steel door and frame, brushed nickel lever handle set, Closer 22 E Von Duprin or comparable. Primed and panted. City choice of color. Doors are to be set to the exterior of the door opening. All exterior wall finish to be replaced to match as existing.

Electrical:

All electrical to be adjusted to be flush with new drywall.

All electrical shall be run within wall. No exposed conduit.

Install new 48 inch 4 bulb led flush mount lights

Pendent lighting to be installed over sinks choice from city with a \$350.00 allowance. Power to be supplied to new lighting to main lighting wall switch.

Signage:

Install ADA compliant men's and women signage on doors and wall.

Bid No. 2

Rock Falls City Hall Restroom Remodel

603 W 10th St, Rock Falls, IL 61071

All finished remodel bathroom to comply with ADA

Demolition:

Remove all fixtures, sinks toilets, grab bars, stall dividers, mirrors, lighting ect.

Remove all wall and floor ceramic tile.

Demo door opening.

Wall finish:

Install ½ inch moisture resistant green board dry wall on all walls, tape and apply smooth finish.

Prime and Paint all walls, city of Rock Falls to supply color choice.

Ceiling finish:

Install ½ inch dry wall on all ceilings, tape and apply smooth finish.

Prime and Paint all walls, city of Rock Falls to supply color choice.

Flooring:

Level all floors and prep for ceramic tile install.

Install Bell Vista 13X13 Smoke ceramic tile in a brick set pattern with a Bell Vista Octagon Mosaic 2 inch Smoke border around all floors 12 inches from wall. Tec #25 sanded grout.

Install Bell Vista Bullnose 3x13 smoke (p43e0) Tec #25 sanded grout.

Plumbing:

Adjust all plumbing per attached ADA layout for bathroom fixtures.

Adjust all floor drains level with new floor tile. Repair all demolition from drain install.

Install new shut offs on all sinks and toilets.

Install Mansfield 410 urinals with a Sloan186-xl and Zurn Zerk-cpm auto flush eye. White color

Install Madera 1.6 gpf ADA EverClean Toilet with a Exposed Manual valve system Mod;2854.016.020 Finish White (020)

Install a 47 Inch Wall-Mount Double Sink Stone Resin Matte White Trough Bathroom Sink with Two Faucet HoleJ020828-GLOSSY_WHITE in the women restroom (<https://www.homary.com/47-inch-wall-mount-double-sink-stone-resin-matte-glossy-white-trough-bathroom-sink-with-two-faucet-hole.html>)

Install a Moen Model # WS84414MSRN Spot resist Brushed nickel faucet

Install a Mona Wall Mounted White single hole sink Model # CeraStyle 064200-U-One Hole in the men's restroom with a Moen Model # WS84414MSRN Spot resist Brushed nickel faucet.

Under sink plumbing shall have ADA protection installed.

All plumbing to be inspected and approved by the Illinois State Health department.

Fixtures:

Install a Rubbermaid Horizontal Baby Changing Station FG781888PLAT in the Women restroom

Install a Bradley Angle Frame Mirror 18x36 over each sink.

Install a Lavex Stainless steel 400 C-Fold Surface mounted Paper Towel Dispenser.

Install solid plastic Stall dividers HDPE City to have choice of color.

Install brushed nickel grab bars per ADA requirements.

Existing hand driers shall be reinstalled.

Existing ceiling vent fans shall be reinstalled.

All fire alarm system to be reinstalled

All Ptech heating and cooling units to be reinstalled.

Install Toilet paper dispensers Kimberly Clark Coreless Double Roll Tissue Dispenser, 11w x 6d x 7 5/8h, Smoke/Gray - KCC09604

Install black Betco Clario hand soap dispensers.

Door:

Install a 36 inch by 80 flush steel door and frame, brushed nickel lever handle set, Closer 22 E Von Duprin or comparable. Primed and panted. City choice of color. Doors are to be set to the exterior of the door opening. All exterior wall finish to be replaced to match as existing.

Electrical:

All electrical to be adjusted to be flush with new drywall.

All electrical shall be run within wall. No exposed conduit.

Install new recessed led lighting in existing openings.

Pendent lighting to be installed over sinks choice from city with a \$350.00 allowance. Power to be supplied to new lighting to main lighting wall switch.

Signage:

Install ADA compliant men's and women signage on doors and wall.

Bid No. 2

Rock Falls Fire Department Restroom Remodel

1013 7th Ave, Rock Falls, IL 61071

All finished remodel bathroom to comply with ADA

Demolition:

Remove all fixtures, sinks toilets, grab bars, stall dividers, mirrors, lighting ect.

Remove all wall and floor ceramic tile.

Demo walls per attached firehouse plan

Demo door openings.

New Wall:

Frame in new walls as attached in plans, 2x 4 construction treated bottom plate.

Wall finish:

Install ½ inch moisture resistant green board dry wall on all walls, tape and apply smooth finish.

Prime and Paint all walls, city of Rock Falls to supply color choice.

Ceiling finish:

Install ½ inch dry wall on all ceilings, tape and apply smooth finish.

Prime and Paint all walls, city of Rock Falls to supply color choice.

Flooring:

Level all floors and prep for ceramic tile install.

Install Bell Vista 13X13 Smoke ceramic tile in a brick set pattern with a Bell Vista Octagon Mosaic 2 inch Smoke border around all floors 12 inches from wall. Tec #25 sanded grout.

Install Bell Vista Bullnose 3x13 smoke (p43e0) Tec #25 sanded grout.

Shower:

Install Bell Vista 13X13 Smoke ceramic tile on all walls and floor Tec #25 sanded grout.

Install ADA shower seat as in attached plans.

Plumbing:

Install shower floor drains.

Install hot and cold water lines to shower controls.

Install a Moen T8375 Commercial Single Handle Posi-Temp All Metal Shower Faucet

Adjust all plumbing per attached ADA layout for bathroom fixtures.

Adjust all floor drains level with new floor tile.

Install new shut offs on all sinks and toilets.

Install Mansfield 410 urinals with a Sloan186-xl and Zurn Zerk-cpm auto flush eye. White color

Install Madera 1.6 gpf ADA EverClean Toilet with a Exposed Manual valve system Mod;2854.016.020
Finish White (020)

Install a Mona Wall Mounted White single hole sink Model # CeraStyle 064200-U-One Hole with a Moen
Model # WS84414MSRN Spot resist Brushed nickel faucet.

Under sink plumbing shall have ADA protection installed.

All plumbing to be installed within walls.

All plumbing to be inspected and approved by the Illinois State Health department.

Fixtures:

Install a Bradley Angle Frame Mirror 18x36 over each sink.

Install a Lavex Stainless steel 400 C-Fold Surface mounted Paper Towel Dispenser.

Install solid plastic Stall dividers HDPE City to have choice of color.

Install brushed nickel grab bars per ADA requirements.

Existing hand driers shall be reinstalled.

Existing ceiling vent fans shall be reinstalled.

All fire alarm system to be reinstalled

Install Toilet paper dispensers Kimberly Clark Coreless Double Roll Tissue Dispenser, 11w x 6d x 7 5/8h,
Smoke/Gray - KCC09604

Install black Betco Clario hand soap dispensers.

Doors:

Install a 36 inch by 80 flush steel door and frame, brushed nickel lever handle set, Closer 22 E Von
Duprin or comparable. Primed and panted. City choice of color. Doors are to be set to the exterior of the
door opening. All exterior wall finish to be replaced to match as existing.

Electrical:

All electrical to be adjusted to be flush with new drywall.

All electrical shall be run within wall. No exposed conduit.

Install new recessed led lighting in existing openings.

All electrical outlets to be updated to GFI.

Pendent lighting to be installed over sinks choice from city with a \$350.00 allowance. Power to be supplied to new lighting to main lighting wall switch.

Install a shower flush mount LED ceiling light, ventilation fan and switch.

Signage:

Install ADA compliant men's and women signage on doors and wall.

Alternate Bid

Rock Falls Fire Department single stall Restroom Remodel

1013 7th Ave., Rock Falls, IL 61071

All finished remodel bathroom to comply with ADA

Demolition:

Remove all fixtures, sinks toilets, grab bars, stall dividers, mirrors, lighting ect.

Remove all wall and floor ceramic tile.

Demo door opening.

Wall finish:

Install ½ inch moisture resistant green board dry wall on all walls, tape and apply smooth finish.

Prime and Paint all walls, city of Rock Falls to supply color choice.

Ceiling finish:

Install ½ inch dry wall on all ceilings, tape and apply smooth finish.

Prime and Paint all walls, city of Rock Falls to supply color choice.

Flooring:

Level all floors and prep for ceramic tile install.

Install Bell Vista 13X13 Smoke ceramic tile in a brick set pattern with a Bell Vista Octagon Mosaic 2 inch Smoke border around all floors 12 inches from wall. Tec #25 sanded grout.

Install Bell Vista Bullnose 3x13 smoke (p43e0) Tec #25 sanded grout.

Plumbing:

Adjust all plumbing per attached ADA layout for bathroom fixtures.

Install floor drain.

Adjust all floor drains level with new floor tile. Repair all demolition from drain install.

Install new shut offs on all sinks and toilets.

Install Madera 1.6 gpf ADA EverClean Toilet with a Exposed Manual valve system Mod;2854.016.020 Finish White (020)

Install a Mona Wall Mounted White single hole sink Model # CeraStyle 064200-U-One Hole in the restroom with a Moen Model # WS84414MSRN Spot resist Brushed nickel faucet.

Under sink plumbing shall have ADA protection installed.

All plumbing to be inspected and approved by the Illinois State Health department.

Install a Bradley Angle Frame Mirror 18x36 over sink.

Install a Lavex Stainless steel 400 C-Fold Surface mounted Paper Towel Dispenser.

Install brushed nickel grab bars per ADA requirements.

Existing hand driers shall be reinstalled.

Existing ceiling vent fans shall be reinstalled.

All fire alarm system to be reinstalled

Install Toilet paper dispensers Kimberly Clark Coreless Double Roll Tissue Dispenser, 11w x 6d x 7 5/8h, Smoke/Gray - KCC09604

Install black Betco Clario hand soap dispensers.

Door:

Install a 36 inch by 80 flush steel door and frame, brushed nickel lever handle set, Closer 22 E Von Duprin or comparable. Primed and panted. City choice of color. Doors are to be set to the exterior of the door opening. All exterior wall finish to be replaced to match as existing.

Electrical:

All electrical to be adjusted to be flush with new drywall.

All electrical shall be run within wall. No exposed conduit.

Install new recessed led lighting in existing openings.

Signage:


Install ADA compliant men's and women signage on doors and wall.

FILE = S:\PROJECTS\2018\18041018 - TRMS\DESIGN\CA\ SHEETS\01 - Cover.dgn

CITY OF ROCK FALLS TOILETROOM ACCESSIBILITY EVALUATION

603 WEST 10TH STREET
ROCK FALLS, ILLINOIS 61071

2018



LOCATION MAP

INDEX OF DRAWINGS

- G1 COVER SHEET
- G2 GENERAL ACCESSIBILITY CODE DETAILS
- G3 CODE PLANS
- 03 TOTAL SHEETS



Know what's below.
Call before you dig.







WILLETT HOFMANN
& ASSOCIATES INC

ENGINEERING ARCHITECTURE LAND SURVEYING

809 EAST 2ND STREET, DIXON, IL 61021-0367
T: 815-284-3381 DESIGN FIRM: #184-000918

WHA NO. 1484D18



DATE: 12-11-2018




STATEMENT OF COMPLIANCE:
I have prepared this drawing and state that, to the best of my knowledge and belief and to the extent of my contractual obligation, this drawing is in compliance with the Environmental Barriers Act (410 ILCS 28) and the Illinois Accessibility Code (71 Ill. Adm. Code 400)


Signed: _____
Date: 12-7-18
Expires: 11-30-2020

PROFESSIONAL SEAL APPLIES TO CODE REQUIREMENTS LISTED ON G3 ONLY AND DOES NOT APPLY TO THE REQUIREMENTS OF ANY OTHER BUILDING CODE OR OTHER BUILDING REQUIREMENTS.
WILLETT, HOPMANN & ASSOCIATES, INC., IS NOT RESPONSIBLE FOR PLUMBING, ELECTRICAL, STRUCTURAL, OR ANY OTHER BUILDING CODE REQUIREMENTS AND IS NOT THE ARCHITECT OR ENGINEER OF RECORD FOR THIS PROJECT.






5 FIREHOUSE EXISTING RESTROOM PLANS
G3 NO SCALE




6 FIREHOUSE PROPOSED RESTROOM PLANS
G3 NO SCALE

MAXIMUM OCCUPANTS
35 MEN AND 15 WOMEN
MEN - 1 TOILET
- 1 URINAL
- 1 LAVATORY
WOMEN - 1 TOILETS
- 1 LAVATORY




7 ADA SHOWER LAYOUT
G3 NO SCALE


FOLDING SHOWER SEAT
SHOWER SEAT TO BE CONSTRUCTED OF MOLDED PLASTIC
WITH A LOAD CAPACITY OF 500#. SHOWER SEAT TO BE
FOLDING TYPE WITH SELF LOCKING MECHANISM AND TYPE
304 STAINLESS FRAMES.





3 ADMINISTRATION BUILDING EXISTING RESTROOM PLANS
G3 NO SCALE



4 CHAMBER OF COMMERCE EXISTING RESTROOM PLANS
G3 NO SCALE





2 CHAMBER OF COMMERCE PROPOSED RESTROOM PLANS
G3 NO SCALE




32 OCCUPANTS
16 MEN AND WOMEN
MEN - 1 TOILET
- 1 URINAL
- 1 LAVATORY
WOMEN - 2 TOILETS
- 1 LAVATORY

1 ADMINISTRATION BUILDING PROPOSED RESTROOM PLANS
G3 NO SCALE



176 OCCUPANTS
88 MEN AND WOMEN
MEN - 1 TOILET
- 1 URINAL
- 1 LAVATORY
WOMEN - 2 TOILETS
- 1 LAVATORY



REVISIONS

NO.	DATE	BY	REVISION

WILLET HOPMANN
ARCHITECTS, P.C.
1000 W. 10TH AVENUE, SUITE 200
DENVER, CO 80202
TEL: 303.733.1100
WWW.WHOPMANN.COM

CITY OF ROCK FALLS
600 W. 10TH AVENUE, SUITE 200
DENVER, CO 80202
PROPOSED TOILETROOM PLANS

PHASE
 PRELIM
 FINAL
 CONGT
 RECORD
 FILE No.
 ENV. No.
 WHA No.
 148-0218
 DATE
 1-22-2019
 SHEET No.
 G3

City of Rock Falls Restroom Remodel Bid Sheet

Contractor Name _____

Address _____

Phone number _____

Bid No.1

Rock Falls Chamber Restroom Remodel

Bid 1 Total _____

Bid No. 2

Rock Falls City Hall Restroom remodel

Bid Total _____

Rock Falls Fire Department Restroom Remodel

Bid Total _____

Bid 2 Total _____

City of Rock Falls Fire Department Alternate Bid

Bid Total _____

PREVAILING WAGE CERTIFICATION

Contractor –

Owner-- City of Rock Falls, Illinois

Contractor agrees that not less than the prevailing rate of wages, as found by the Department of Labor of the State of Illinois, shall be paid to all laborers, workers and mechanics performing work under the contract, and Contractor agrees that all subcontracts and lower tiered subcontracts shall contain a written stipulation that not less than the prevailing rate of wages shall be paid to all laborers, workers and mechanics performing work under such subcontract or lower tiered subcontract, all as determined by the Department of Labor of the State of Illinois.

Contractor also agrees that it shall:

1. Make and keep for a period of not less than three (3) years, records of all laborers, mechanics and other workers employed on the project, including each worker’s name, address, telephone number when available, social security number, classification or classifications, hourly wages paid in each pay period, number of hours worked each day, and the starting and ending times of work each day; and
2. Submit no later than the 15th day of each calendar month a certified payroll for the immediately preceding month with the City Clerk until such time the Illinois Department of Labor activates their database at which time certified payrolls shall be only submitted to that database.

At the time of request for each progress payment, Contractor shall deliver to Owner a contractor’s affidavit listing all suppliers of labor and material, the work performed by each, the amounts paid to each to date, the amount due for work performed to date and a waiver of lien for any payments made to any such supplier signed by such supplier.

Contractor:

Owner:

City of Rock Falls, Illinois

By: _____

By: _____

President

Mayor

CERTIFICATE OF COMPLIANCE STATEMENT

The undersigned, upon being first duly sworn, hereby certifies to the City of Rock Falls, Whiteside County, Illinois, that _____(bidder) shall comply with all of the following established compliance standards.

1. Certificate of Compliance with Safety Standards
2. Certificate of Compliance that the above bidder is not currently delinquent in the payment of any tax administered by or owed to the Illinois Department of Revenue, or otherwise in default upon any such tax as defined under CH.65, Sec. 11-42.1-1, Illinois Compiled Statutes.
3. Certificate of Compliance that the above bidder complies with the Illinois Human Rights Act as amended by Section 2-105, Public Act 87-1257 in relation to employment and human rights.
4. Certificate of non-Disqualification certifying that the above named bidder is not barred from contracting with any unit of State or local government, as a result of a violation of Ch. 720, Sec. 33E-11 of the Illinois Compiled Statutes.

NOTE TO BIDDER: Anyone who makes a false statement, material to this Certification, commits a Class 3 Felony under Illinois Compiled Statutes, Ch. 720, Sec. 33E-11 (b).

5. Certificate of Compliance with Prevailing Wage Rate Act certifying that all work under this contract shall comply with the Prevailing Wage Rate Act of the State of Illinois, Illinois Compiled Statutes, Chapter 820, par. 130/31. et. seq., and as amended by Public Act 86-799 and 86-693 with rates to be paid in effect at time work is performed. Contractors shall submit monthly certified payroll records to the Office of the City Clerk.

Name of Contractor

By: _____

State of Illinois)
)
County of _____)

Subscribed and sworn to before me this _____ day of _____, 20____.

Notary Public

CITY OF ROCK FALLS
Certificate of Insurance Requirements

All Contractors, manufacturers/distributors and suppliers shall be required to carry and evidence insurance coverage with a standard Accord Certificate of Insurance with minimum limits applicable as outlined below. These Tier amounts shall be decided and required by the Department Head using the knowledge of the potential risks associated with the project being bid.

1. Minimum Insurance Requirements and limits

I. Low Hazard

A. Commercial General Liability	\$1,000,000
B. Automobile Liability	\$1,000,000
C. Workers Compensation	\$1,000,000
D. City of Rock Falls named as "Additional Insured"	
E. 60 days' notice of cancellation	
F. Hold Harmless Agreement included in contract	
G. Umbrella Liability	\$1,000,000

II. Medium Hazard

A. Commercial General Liability	\$2,000,000
B. Automobile Liability	\$2,000,000
C. Workers Compensation	\$2,000,000
D. City of Rock Falls named as "Additional Insured"	
E. 60 days' notice of cancellation	
F. Hold Harmless Agreement included in contract	
G. Umbrella Liability	\$2,400,000

III High Hazard

A. Commercial General Liability	\$3,000,000
B. Automobile Liability	\$3,000,000
C. Workers Compensation	\$3,000,000
D. City of Rock Falls named as "Additional Insured"	
E. 60 days' notice of cancellation	
F. Hold Harmless Agreement included in contract	
G. Umbrella Liability	\$9,000,000

1. Cancellation or Alteration

The policies of insurance required by this exhibit shall provide that they cannot be cancelled or altered in any way changing coverage except after 30 days prior written notice by certified mail to owner.

2. Workers' Compensation and General Liability Waiver of Subrogation in favor of the City of Rock Falls.

3. Insurance Certificates

A. Must be submitted ten (10) days prior to any work being performed to allow review of certificates.

B. Certificates not meeting requirements must be revised and resubmitted within fifteen (15) days or the subcontractor will not be allowed on the jobsite.

4. Additional Insured and Broad Form Vendors' Liability in favor of the City of Rock Falls.

The City must be named as an Additional Insured with the following wording appearing on the Certificate of insurance: "The City of Rock Falls and all officials and employees of the City as to any and all projects, as an additional Insured for the Commercial General Liability as respects and all projects for any work being performed and this coverage will be primary and noncontributory."

5. Minimum Insurance Carrier

All contractors, manufacturers/distributors and suppliers' insurance carriers must comply with the minimum A.N. Best rating of A-VI for all insurance carriers.